Abstract Notification, dated 25th December 1935.

The attention of the public is invited to the Notification calling for tenders for enclosing the open courtyard in the First Floor of the District Office building and forming two halls at Bangalore, published on pages 13-14 of Part VI of the *Mysore Gazette*, dated 2nd January 1936.

The last date of receiving tenders is 22nd January 1936.

N. KRISHNA IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 26—27th December 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 13th January 1936, for constructing Electric Buildings at Hoskote Town, Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Electric Buildings at Hoskote Town, Hoskote Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7 The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of approximate quantities required for constructing Electrical Buildings at Hoskote, (Bangalore District).

Sl. No.	Items of Work	Per	Quantity	Sanctioned rate	Rate in Figures	Rate in Words
				Rs. a. p.		
	I. Constructing an Office and Stores for Rural Towns with a Bath room attached at Hoskote Town.					
1	Earthwork excavation and filling in basement	C.yd.	32	0 3 3		
2	(*a*) Stone jelly concrete in mortar for foundation	C.ft.	257	0 3 9		
	(*b*) Coursed rubble stone masonry in mortar with through stones introduced at 6 ft. intervals in every course ..	,,	818	0 4 6		
	(*c*) Burnt brick in clay superstructure ..	,,	1,262	0 3 6		
	(*d*) Burnt brick in mortar superstructure ..	,,	287	0 4 3		
	(*e*) Burnt stone slabs 4" thick exposed parts dressed and fixed in mortar ..	S.ft.	96	0 5 0		
	(*f*) Plastering with lime mortar, two coats	Sqr.	29·28	3 0 0		

Sl. No.	Items of Work	Per	Quantity	Sanctioned rate	Rate in Figures	Rate in Words
				Rs. a. p.		
	(*g*) Chunnam pointing with thread lines ..	Sqrs.	1·96	1 8 0		
	(*h*) White and colour washing, two coats ..	,,	31·24	0 4 6		
	(*i*) Binding wall $1\frac{1}{8}' \times \frac{3}{4}'$ with burnt brick in mortar with chunam plaster white-wash, etc., complete	R.ft.	42	0 6 0		
	(*j*) Chunnam patty borders $6'' \times 3''$ over verandah	,,	20	0 2 0		
	(*k*) Cornice with burnt brick in mortar plain 6″ deep with chunnam plaster, whitewash, etc., complete	,,	42	0 5 0		
	(*l*) Burnt brick in mortar parapet wall 9″ thick with chunnam plaster, white-wash, etc., complete as per design ..	,,	19	0 14 0		
	(*m*) Burnt brick in mortar cornice 9″ deep including chunnam plastering, white-wash, complete as per design ..	,,	22	0 8 0		
3	(*a*) Flooring with 1st Class Mangalore square tiles on 3″ concrete bed and cement pointed including thread lining ..	Sqr.	4·02	30 0 0		
	(*b*) Flooring with cuddapah slabs $1\frac{1}{2}''$ thick on 3″ stone jelly lime concrete bed and cement pointing including thread lining	,,	1·94	28 0 0		
	(*c*) Flooring with $1\frac{1}{2}''$ thick cement concrete over 3″ stone jelly lime concrete and plastered with cement mortar $\frac{1}{2}''$ thick mixed with red ochre and finished smooth with tiles cut, etc., complete	,,	5·96	22 0 0		
4	(*a*) Roofing with 1st Class Mangalore tiles on teakwood reepers and $2'' \times 1''$ including two coats of wood oiling to reepers	,,	9·16	24 0 0		
	(*b*) Ridging with Mangalore tiles set in mortar including cement pointing ..	R.ft.	28	0 8 0		
4	(*c*) *i*. Roofing with cuddapah slabs $1\frac{1}{2}''$ thick with 3″ brick concrete and two courses of flat tiles, top plastered, ceiling cement pointed and whitewashed etc., complete	Sqr.	0·44	32 0 0		
	ii. Roofing with reinforced brick work with weathering coat and two courses of flat tiles, etc., complete as per specification	,,	0·44	60 0 0		
	(*d*) *i*. Mysore teakwood wrought and put up with two coats of wood oiling ..	C.ft.	37·66	5 0 0		
	ii. Mysore teakwood cut scandlings will be supplied departmentally at Forest Department, Mysore. Quotations may be given only for transportation joinery and carpentry charges including fixing at site with two coats of wood oiling	,,	37·66	..		
	(*e*) Teakwood eaveboard plain $8'' \times 1''$ including two coats silicate painting..	R.ft.	56	0 6 0		
	(*f*) Teakwood doors with pannelled shutters $1\frac{1}{2}''$ thick with bolts, hinges, clamps, and iron fittings, etc., complete	S.ft.	74	1 12 0		
	(*g*) Teakwood windows with pannelled shutters $1\frac{1}{4}''$ thick in four halves with iron bars $\frac{3}{4}''$ dia. with hinges, clamps, and iron fittings, etc., complete ..	,,	70	2 0 0		
	(*h*) Teakwood ventilators glazed with iron bars $\frac{3}{4}''$ dia. with clamps and fittings, etc., complete	,,	14	1 4 0		
	(*i*) Silicate painting, two coats ..	Sqr.	4·69	4 0 0		
5	Rolled steel joists (Tata's) including hoisting, fixing, painting, etc., complete ..	Cwt.	4·2	11 0 0		
6	Zinc sheet 22 gauge rain water down-pipes fixed with clamps, etc., complete ..	R.ft.	12	0 6 0		

Sl. No.	Items of work	Per	Quantity	Sanctioned rate	Rate in Figures	Rate in Words
				Rs. a. p.		
7	Providing and fixing expanded metal ¾" mesh shutters including fittings, etc., complete	S.ft.	63	0 12 0		
8	Sun shades for windows made of plain zinc sheet 22 gauge fixed on teakwood frames including two coats of silicate painting..	Each	4	5 0 0		
	II. Constructing Operators' Quarters at Hoskote.					
1	Earthwork excavation and filling in basement	C.yd.	33	0 3 3		
2	(*a*) Stone jelly concrete in chunnam mortar.	C.ft.	315	0 3 9		
	(*b*) Burnt size stone in clay for foundation and basement	,,	705	0 3 6		
	(*c*) Burnt brick in clay superstructure ..	,,	2,044	0 3 6		
	(*d*) Burnt stone slabs 4" thick dressed and fixed in mortar	S.ft.	119	0 5 0		
	(*e*) Chunnam plastering two coats ..	Sqr.	42·22	3 0 0		
	(*f*) Chunnam pointing with thread lines ..	,,	1·09	1 8 0		
	(*g*) White and colour washing two coats ..	,,	43·31	0 4 6		
	(*h*) Constructing sinks with burnt brick in mortar including plastering, etc., complete	Each	1	5 0 0		
	(*i*) Providing and fixing stone mortar and pestle	,,	1	6 0 0		
	(*j*) Cornice with burnt brick in mortar 6" deep including chunnam plastering, whitewash, etc., ...	R.ft.	60	0 5 0		
	(*k*) Binding wall $1\frac{1}{8}' \times \frac{3}{4}'$ with burnt brick in mortar with chunnam plaster, whitewash, etc., complete	,,	60	0 6 0		
3	(*a*) Roofing with 1st Class Mangalore Tiles on teakwood reepers 2"×1" including two coats wood oiling to reepers ..	Sqr.	8·00	24 0 0		
	(*b*) Ridge tiles set in mortar and cement pointed	R.ft.	24	0 8 0		
	(*c*) Providing and fixing ventilating tiles ..	Each	2	2 6 0		
4	(*a*) Honneywood wrought and put up with two coats of wood oiling	C.ft.	30·20	3 12 0		
	(*b*) Teakwood door frames with honneywood battened shutters 1" thick including hinges, bolts, clamps and iron fittings, etc., complete	S.ft.	156	1 6 0		
	(*c*) Teakwood window frames with honneywood battened shutters with ¾" dia. iron bars including iron clamps and fittings, etc.	,,	78	1 8 0		
	(*d*) Silicate painting two coats	Sqr.	5·85	4 0 0		
5	Flooring with 1½" thick cement concrete over 3" stone jelly lime concrete and plastered with cement mortar ½" thick mixed with red ochre and finished smooth with tiles cut, etc., complete	,,	4·93	10 0 0		
	III. Constructing one Block of Cooly Quarters to accommodate two Coolies at Hoskote.					
1	Earthwork excavation and filling in basement	C.yd.	20	0 3 3		
2	(*a*) Stone jelly concrete in chunnam mortar.	C.ft.	219	0 3 9		
	(*b*) Burnt size stone in clay for foundation and basement	C.ft.	508	0 3 6		
	(*c*) Burnt brick in clay superstructure ..	,,	1,471	0 3 6		
	(*d*) Burnt stone slabs 4" thick roughly dressed and fixed in mortar ..	S.ft.	92	0 5 0		

Sl. No.	Items of Work	Per	Quantity	Sanctioned rate	Rate in Figures	Rate in Words
				Rs. a. p.		
	(e) Chunnam plastering 2 coats	Sqr.	28·67	3 0 0		
	(f) Chunnam pointing with thread lines ..	,,	1·00	1 8 0		
	(g) White and colour washing, 2 coats ..	,,	29·67	0 4 6		
	(h) Providing and fixing stone mortar and pestle	Each	2	6 0 0		
	(i) Constructing sinks with burnt brick in mortar including cement plastering, etc., complete	,,	2	5 0 0		
	(j) Binding wall $1\frac{1}{8}' \times \frac{3}{4}'$ with burnt brick in mortar with chunnam plaster white-wash, etc., complete at the end of roof.	R.ft.	40	0 6 0		
	(k) Chunnam patty borders at end of veran-dah roof	,,	18	0 2 0		
	(l) Cornice with burnt brick in mortar 6″ deep including chunnam plastering, whitewash, etc.	,,	40	0 5 0		
3	(a) Roofing with 1st class Mangalore Tiles Teakwood reepers 2″×1″ including 2 coats of wood oiling to reepers ..	Sqr.	768	24 0 0		
	(b) Ridging with Mangalore Tiles set in mortar including cement pointing ..	R.ft.	25	0 8 0		
	(c) Providing and fixing Mangalore Venti-lating Tiles including cement pointing.	Each	8	2 6 0		
4	(a) Honneywood wrought and put up with 2 coats of wood oiling	C.ft.	2577	3 12 0		
	(b) Teakwood door frames with honney-wood battened shutters 1″ thick includ-ing hinges, bolts, clamps, and iron fit-tings, etc., complete	S.ft.	39	1 6 0		
	(c) Teakwood window frames with honney-wood battened shutters with $\frac{3}{4}$″ dia. iron bars including iron clamps and fittings, etc., complete	,,	50	1 8 0		
	(d) Silicate painting, two coats	Sqr.	180	4 0 0		
5	Flooring with $1\frac{1}{2}$″ thick cement concrete over 3″ stone jelly lime concrete and plastered over with cement mortar $\frac{1}{2}$″ thick mixed with red ochre and finished smooth with tiles cut ..	Sqr.	400	10 0 0		
	IV. Constructing one unit of Latrines for small Town Installations at Hoskote.					
1	Earthwork excavation	C.yd.	4	0 3 3		
2	(a) Burnt size stone in clay foundation and basement	C.ft.	130	0 3 6		
	(b) Burnt brick in surki mortar superstruc-ture	,,	196	0 4 3		
	(c) Surki mortar plastering	Sqr.	4·91	3 0 0		
	(d) Surki mortar pointing	,,	0·56	1 8 0		
	(e) White and colour washing, 2 coats ..	,,	5·47	0 4 6		
	(f) Cement plastering $\frac{1}{2}$″ thick	,,	0·79	8 0 0		
	(g) Tar wash, 2 coats	,,	0·63	1 4 0		
	Flooring $1\frac{1}{2}$″ thick cement concrete over 3″ stone jelly lime concrete and plastered with cement mortar $\frac{1}{2}$″ thick and finished smooth and even	Sqr.	0·38	10 0 0		
4	Fixing outlets and constructing drains ..	L. S.	..	10 0 0		
5	Providing and fixing galvanised iron sheet tubs 12″×6″ complete with tarring ..	Each	6	2 0 0		

M. A. SRINIVASACHARI,
Executive Engineer.